



Total Camber = 1 3/4"
Approved as corrected: Richard A. Bruce, P.E.
Deputy Co. Engineer

- NOTES:
1. CONC. STR. AT TIME OF PRESTRESSING = 4000 P.S.I. @ 28 DAYS = 5500 P.S.I.
 2. DETENSION STRAND SYMMETRICALLY ABOUT CENTER LINE
 3. WATERPROOF BEAM ENDS
 4. OMIT KEYWAY ON EXTR FACE OF EXTR BEAMS
 5. LOADING = H5-20-44
 6. BEAM WEIGHT = 64,300 lbs.
 7. TOP SURFACE OF BEAMS GIVEN A FLAT FLOAT FINISH.
- CHANGE NOTES: Changes Are Noted As Different From O.D.O.T. Std. Dwg. P.S.B.D.-1-81 & Are Varied Per Note On Dwg. P.S.B.D.-1-81 Sht. 2 of 4.
1. 6/16" KEYWAY TO 4" x 4" KEYWAY
 2. TIE ROD HAND HOLE FROM 1'-2" TO 10"

REVISIONS		Br. No. LOG-CR-121-2.65 — Logan Co., Oh.	
NO.	DATE	BY	Contractor - The Sherburn Co.
1.			SCALE NONE PRESTRESS SERVICES, INC.
2.			DATE 11-5-85 Decatur Indiana
3.			DRAWN BY B.A. JOB NO. DRAWING NO.
4.			CHECKED BY J.R.H. 1444 SH. 1 OF 1

P.C. 9264