



- NOTES:
1. CONC. STR. AT TIME OF PRESTRESSING = 4000 P.S.I. @ 28 DAYS = 5500 P.S.I.
 2. DETENSION STRAND SYMMETRICALLY ABOUT CENTER LINE
 3. WATERPROOF BEAM ENDS
 4. OMIT KEYWAY ON EXTR FACE OF EXTR BEAMS
 5. LOADING = 45-20-44
 6. BEAM WEIGHT = SEE BEAM PLANS
 7. TOP SURFACE OF BEAMS GIVEN A FLAT FLOAT FINISH.
- CHANGE NOTES: (PER NOTE ON QDDT STD DWG. P.S.B.D. - 1-81 SHIT 2 OF 4.)
1. 6/16" KEYWAY TO 4/4" KEYWAY
 2. TIE ROD HAND HOLE FROM 1.2" TO 10"
 3. 3" TIE ROD HOLE TO 2" TIE ROD HOLE

REVISIONS			Br. No. 131-072 Logan Co., Ohio	
NO.	DATE	BY	Contractor - Logan Co. Forces	
1.			SCALE NONE	PRESTRESS SERVICES, INC.
2.			DATE 9-7-83	Decatur Indiana
3.			DRAWN BY B.A.	JOB NO. 3044 DRAWING NO.
4.			CHECKED BY J.R.H.	54 OF 1

P.C. # 9264